Animal Conservation | ZSL
LIVING CONSERVATION

Controlling Access to oil-roads protects forest cover but not wildlife communities: a case study from the rainforest of Yasuní Biosphere Reserve (Ecuador)

SCHOLARONE™
Manuscripts

Controlling Access to oil-roads protects forest cover but not wildlife communities: a case study from the rainforest of Yasuní Biosphere Reserve (Ecuador)

Esteban Suárez
Colegio de Ciencias Biológicas y Ambientales, Universidad San Francisco de Quito
esuarez@usfq.edu.ec

Galo Zapata-Ríos
Department of Wildlife Ecology and Conservation, University of Florida, and Wildlife Conservation Society-Ecuador

Víctor Utreras
Wildlife Conservation Society-Ecuador

Samantha Strindberg
Wildlife Conservation Society

and

Javier Vargas
Ministerio del Medio Ambiente del Ecuador

Running title: Indirect impacts of oil-roads on wildlife
Manuscript body: 4405 words
Number of Figures: 2
Number of Tables: 2

Corresponding author:

Esteban Suárez
Colegio de Ciencias Biológicas y Ambientales, Universidad San Francisco de Quito.
Avenida Diego de Robles S/N e Interoceánica.
Phone: (+593) 2 297-1700 ext. 1444
Fax: (+593) 2 297-1700
esuarez@usfq.edu.ec

1

Abstract

Through the analysis of a case-study from Amazonian Ecuador, this paper evaluates the impacts of two oil-road management approaches on the structure and composition of wildlife communities (large or medium sized mammals and game bird species). In a free-access road, where forest has been cleared and fragmented by colonists, fewer species were found, together with wildlife density estimates that were almost 80% lower than on a Control site without human disturbance. In contrast, on the road where access control has been enforced, habitat destruction has been minimal, but several wildlife species showed reductions in their populations, apparently related to changes in the subsistence practices of local Waorani hunters that settled along the road after its construction. In this area, economic subsidies and free transportation from the oil companies, access to the road, more efficient hunting technologies, and market incentives have increased the impacts of hunting by the Waorani, resulting in depletion of the local wildlife populations. Our research suggests that construction of roads in oil extraction areas must be avoided if at all possible. The alternative management of controlling access can be effective for short-term habitat protection, but not for wildlife conservation, especially when oil industry practices alter the social dynamics of local indigenous groups.

2

Introduction

Throughout the world, conservation of wildlife communities is challenged by an increasing

overlap between human-dominated landscapes and the remnants of pristine habitats. While

analyzing the impacts of this overlap, previous research has emphasized the more obvious and

direct impacts of large human interventions such as expansion of the agricultural frontier, timber

extraction, and the resulting loss and fragmentation of habitats (Bonaudo, Le Pendu, Faure *et al.*,

2005b, Lopes & Ferrari, 2000, Ochoa, 2000, Taylor & Goldingay, 2010). Because of their nature

and magnitude, these human interventions leave little or no habitat available for wildlife species,

with obvious effects on the composition, structure and abundance of their communities. In

contrast, comparatively little attention has been paid to the *indirect effects* of other human

activities (*e.g.* extractive industries) that could have dramatic long-term effects on wildlife

communities, usually mediated by i) changes in the accessibility to the landscape (*i.e.* roads), ii)

changes in the subsistence practices of local human communities (Franzen & Eaves, 2007, Lu,

1999), and iii) alteration of the economic frameworks that govern the interactions between local

people and wildlife (Godoy, Undurraga, Wilkie *et al.*, 2010, Thibault & Blaney, 2003).

As we consider the indirect effects of extractive industries in or near wildlife sanctuaries, oil and

gas exploitation emerge as one of the most striking examples of the intricate conflicts arising

from the overlap of wildlife refuges and other ecologically important areas, with the huge

economic interests brought about by an ever-growing industry that support national economies.

From the ecological devastation inflicted by the 2010 oil spill in the Gulf of Mexico (Campagna,

Short, Polidoro *et al.*, 2011, DeLaune & Wright, 2011, Richards, Gardiner, Schmidt *et al.*, 2011),

to the social and legal uproar around the trial against Chevron (TEXACO) over its alleged

3

responsibility for the pollution of a large tract of the Ecuadorian Amazon (Finer, Vijay, Ponce *et al.*, 2009, Olsen, 2001, Valdivia, 2007, Yoder, 2002), the history of oil industry operations in ecologically and culturally sensitive areas is plagued by cases of environmental pollution and ecosystem destruction, social unrest, and a sense of opportunities lost, among those who see potential benefits in collaborations between conservation and industry. But in the midst of the rocketing energy demands world-wide, and the inevitable expansion of the oil industry, research efforts have focused on the assessment of direct impacts of oil spills or other forms of pollution on wildlife and ecosystems, while little is known about the effects of different management alternatives which could mitigate some of the impacts of the activities and infrastructure related to oil. By using a case-study from Yasuní Biosphere Reserve (YBR), in this paper we discuss the differential impacts of two types of management implemented on roads opened to allow oil exploitation in the Ecuadorian Amazon. In particular, we evaluate the effects of road access control in terms of protecting wildlife communities (large or medium sized mammals and game bird species) in lowland Neotropical rain forests in Ecuador.

The effects of roads have been widely analyzed with regards to their direct impacts on wildlife and habitat destruction (Benítez-López, Alkemade & Verweij, 2010, Clevenger, Chruszcz & Gunson, 2003, Coelho, Kindel & Coelho, 2008, Forman & Alexander, 1998, Goosem, 2002, Greenberg, Kefauver, Stimson *et al.*, 2005, Jones, 2000, Laurance, Goosem & Laurance, 2009, Spellerberg, 1998, Taylor & Goldingay, 2010). Road construction has immediate impacts on wildlife mobility and mortality, and direct effects on forest cover, which are usually small in terms of total area impacted. Moreover, roads provide access to previously remote regions, thus facilitating colonization, deforestation, exploitation of wildlife, and agricultural encroachment

4

(Bonaudo, Le Pendou, Faure *et al.*, 2005a, Laurance *et al.*, 2009, Nepstad, Carvalho, Barros *et al.*, 2001, Southworth, Marsik, Qiu *et al.*, 2011). Furthermore, roads usually promote commercial exchange among newly connected areas, accelerating habitat destruction and further intensifying hunting and its impacts on wildlife (Suárez, Morales, Cueva *et al.*, 2009; but see Ayres, de Magalhaes, de Souza *et al.*, 1991). In the rainforests of Gabon, for example, hunting associated with the presence of roads reduced population abundance and changed the behavior of several large-bodied mammals (Laurance, Croes, Tchignoumba *et al.*, 2006). Similarly, proximity to the access matrix (roads and rivers) in the Brazilian Amazon has been shown to predict the abundance of game species, whose abundances were depressed in areas that are closer these transportation axes (Peres & Lake, 2003). While these impacts are well documented, there is virtually no information about factors, such as access and road-use restrictions, that could help mitigate some of their negative impacts.

The Ecuadorian Amazon, with its exceptional levels of wildlife diversity, the presence of sensitive indigenous groups, and the influence of an active oil industry, provides an excellent setting to explore the interactions that emerge in areas where cultural and ecological integrity are confronted with the changes that the oil industry bring. At the same time, given the heterogeneity of oil exploitation approaches and policies that have been implemented, this area is ideal to explore mechanisms or practices that could minimize the negative impacts that this economic alternative has on native ecosystems and human communities. In particular, YBR offers an unusual opportunity to consider mechanisms or practices that could minimize the negative impacts of oil exploitation on native ecosystems and human communities. In a previous paper (Suárez *et al.*, 2009) we explored the structure of a wild-meat market that emerged in the YBR,

5

and its relationship with the roads and the operation of oil companies in this region. At that time, however, we did not have enough information to assess the effects of this market on the local wildlife communities. In this paper, we discuss new information on the impacts of these roads by comparing the efficacy of road control policies in terms of reducing deforestation and wildlife depletion in natural areas of tropical lowland forests in eastern Ecuador. With this objective, we discuss the results of wildlife surveys in the area of influence of two contrasting roads in the YBR: the "Auca" road, which is an open-access road built in the early 1970s, and the "Maxus" road, which is a controlled road begun in 1992 into the core of this protected area.

Methods

Yasuní Biosphere Reserve (~ 76º00'W, 01º00'S) is located in the Ecuadorian Amazon at elevations ranging from 200 to 500 m (Figure 1), and has been recognized as a globally important area for biodiversity conservation (Bass, Finer, Jenkins *et al.*, 2010). The reserve, composed of Yasuní National Park (YNP) and the contiguous Waorani Ethnic Reserve, encompasses an area of approximately 18,000 km^2, with warm climate and 3,500 mm of annual precipitation typically described as aseasonal. The landscape is dominated by *terra firme* forest divided by small areas of floodplain, swamp, and successional forest (Balslev & Renner, 1989).

To evaluate the effects of two oil-road management approaches, we focused our research in three areas of the YBR (Figure 1): (i) Taracoa, located on one of the branches of the Auca Road, (ii) Yasuní Scientific Station, located on the southern bank of Tiputini River, at km 52 of the Maxus Road; and (iii) a Control site without recent human disturbance, located along the Tiputini River. The maximum distance between these areas is roughly 89 km, and they are all dominated by

6

terra firme forests with uniform structure and composition. These sites, however, differ in the amount of disturbance that they have experienced: the Auca road was built in 1972 to allow oil exploitation in the region to the west of YNP, and triggered an uncontrolled flood of colonists, resulting in deforestation rates of about 4% per year between the 1970s and 1990s (Wunder, 1997), and an approximate forest loss of 40% in the vicinity of the road (GeoPlaDes, 2010). In contrast, the 140 km Maxus road was built in 1992 to allow oil exploitation inside YBR itself. Before the road construction, the only significant impacts on this area were occasional subsistence hunting events by the Waorani groups that occupied the region. However, the low densities of these groups and their semi-nomadic customs suggest that these hunting practices had a negligible impact on wildlife communities (Vickers, 1988, Yost & Kelley, 1983). After construction of the Maxus road, the oil company established a control policy, which limited the access of outsiders and the impacts of colonization. The new road, however, attracted local Waorani people who settled along the road and use it as a hunting corridor. Thus, while the control strategy in this road was effective in terms of avoiding colonization and deforestation (until 2005, less than 2% of the forest had been lost (Greenberg *et al.*, 2005), cultural changes among the Waorani and the transportation subsidies that they receive from the oil company, turned them into major suppliers of bushmeat to the market located at the origin of the road (Suárez *et al.*, 2009).

To estimate the density of wildlife populations, from April 2005 to July 2006 we carried out a series of bi-monthly surveys of large birds (several cracid species, toucans, and the grey-winged trumpeter), and medium-sized and large mammals (> 1 kg). Surveys were performed using distance sampling techniques along six line transects (2 km each) in each of the three sampling

7

sites (Buckland, Anderson, Burnham *et al.*, 2001). Each transect originated and continued

perpendicularly from the roads (Taracoa and Yasuní Research Station) or from the river (Control

site).

Each transect was surveyed during the morning (06:00 – 08:00 hrs) and evening (18:00 – 20:00

hrs) during eight time periods, by teams of three people walking slowly (~ 1 km/hr) and

recording direct wildlife observations. To avoid violating the assumption of certain detection

near or close the transect line, observers paid particular attention to these areas, especially for

birds and primates potentially hidden by thick foliage. To standardize efforts, surveys were not

conducted during rainy days (Peres, 1999). For each observation, we recorded the species,

number of individuals in the group, as well as sighting radial distance and angle to the center of

the group (attempts were made to obtain these measurements accurately before any responsive

movement occurred to avoid biased estimates of density and abundance). If the species occurred

in groups, the perpendicular distance to the center of the group was recorded. The analysis was

conducted using Distance 5.0 Beta 3 (Thomas, Buckland, Rexstad *et al.*, 2010). Population

densities were derived by applying uniform and half-normal key functions, and cosine or simple

polynomial adjustment terms as needed. Due to low encounter rates for most species, data were

pooled over the eight time periods according to taxonomic ranks (Order) to fit detection

functions (with further pooling across Orders for some of the bird species). Goodness of fit tests

were used to identify violations of assumptions. Akaike's Information Criterion (AIC) was used

in model selection, with particular attention paid to model fit at distances near zero since the fit

of the shoulder near zero is most important for robust estimation (Buckland, Anderson, Burnham

et al., 2001). Encounter rate was estimated separately for each site by species, but pooled over

8

time. A Poisson distribution was assumed to estimate the variance in encounter rate. Group size

was estimated separately for each species pooled over time and sites, unless ANOVA indicated

that group size varied significantly by site, in which case site-specific estimates were used.

Average group size was used, unless the test for size bias at the 10% level of significance

(determined by means of a regression of the natural logarithm of group size against distance

from the transect line) indicated that expected group size was more appropriate. Density of

groups and of individuals by species for each of the three sites was estimated. Biomass for each

species was calculated using average density estimates derived from our surveys, which were

multiplied by the mean body weight reported in the literature for each species (Emmons, 1999).

Results

After a total sampling effort of 254 km, we recorded 268 individuals belonging to 24 species

(sighting rate: 1.06 sightings/km). Large variation in sample size was observed among species,

from one observation each for five species (*Alouatta seniculus*, *Saguinus fuscicollis*, *Nothocrax

urumutum*, *Ortalis guttata* and *Cuniculus paca*) to 32 observations for *Sciurus* spp. Even pooling

the data by order (or across orders for some of the bird species), after right truncation to improve

model fit, we only reached the upper limit of the recommended sample size for primates, just

over half that limit for the bird and rodent species and under a quarter for Artiodactyla (see

Figure 2 for details of each detection function fit). Even so, the detection functions were

reasonable with the possible exception of that for Artiodactyla.

Species composition and abundance exhibited important differences. Overall, in the highly

impacted area along the Auca road we recorded fewer species than in the other two sites, and

9

wildlife densities one half that of the Maxus road, and one quarter that of the Control site (Table 1). Among the most notable species that were absent from our surveys on the Auca road are three primate species previously reported for this region (*Ateles belzebuth*, *Lagothrix lagotricha*, and *A. seniculus*), and the white-lipped peccary (*Tayassu pecari*). In the case of the Maxus road, species composition in this area was relatively similar to that in the Control site, with the exception of the absence of the white-lipped peccary, Salvin´s curassow (*Mitu salvini*) and the speckled chachalaca (*Ortalis guttata*), which were not directly recorded along the transects in this area. However, our density estimates for most of the species was much lower on the Maxus road (Table 2), resulting in total wildlife densities that were 2.4 times lower at the Maxus site (110 ind./km^2) than at the Control (265 ind./km^2). Of the 24 species reported, 11 exhibited higher average densities in the Control that within the Maxus or Auca road sites, whereas only four species were more abundant along the Maxus road than in the Control site (Table 1).

Differences between faunal communities in the three sites are even more striking when analyzing wildlife biomass estimates. At the Control site we estimated a total biomass of 4380 kg/km^2, with almost 87% being contributed by the white-lipped peccary (Table 2). However, even if we exclude this large bodied and gregarious species from the analysis, the Control wildlife biomass estimate (509 kg/km^2) was 1.7 times greater than on the Maxus road (295 kg/km^2), and six times greater than in the Auca road site (84 kg/km^2). Most of this biomass decline is due to smaller populations of large bodied monkeys, ungulates, and game bird species.

10

Discussion

Although line-transects have been used in several Neotropical localities (Carrillo, Wong & Cuarón, 2000, Cullen, Bodmer & Valladares-Padua, 2001, Peres, 2000b), when encounter rates are low this sampling technique can require considerable survey effort to obtain adequate sample sizes to fit detection function models (Buckland *et al.*, 2001, Peres, 1999). Although, our sample sizes were relatively small, our density estimates lie in the same range as those from other Neotropical areas (Cullen *et al.*, 2001, Hill, Padwe, Bejyvagi *et al.*, 1997, Peres, 2000b). Given our relatively small sample sizes, our discussion emphasizes not the overall density or biomass estimates for each species, but the relative differences between sites in terms of species composition and estimated density and biomass, derived from equal sampling efforts and survey methods.

The purpose of this study was to use a case study in Amazonian Ecuador to assess if controlling access to roads in oil extraction areas was enough in terms of avoiding detrimental impacts on tropical wildlife communities, with emphasis on large or medium sized mammals and game bird species. Although access control to the Maxus road in the YNP has been shown to be an effective strategy in terms of restricting colonization, forest loss, and habitat fragmentation (only between 2 and 7% of the area has been deforested in the vicinity of the road (GeoPlaDes, 2010, Greenberg *et al.*, 2005), our data suggest that wildlife has been severely impacted in this area, underscoring the importance of the indirect effects associated with the presence of roads and the oil industry.

11

The lack of fauna at the Auca road site was no surprise, as this area has been subjected to forest clearing and fragmentation, and intense hunting since its construction. In this area, open access to the roads resulted in rapid colonization and the ensuing deterioration of wildlife communities, as evidenced by the apparent absence of at least 11 species, never observed during this study. Interestingly, the species lost along the Auca road include not only hunting-sensitive species, but also small species such as titi monkeys, squirrels, and toucans, whose absence from this area probably reflects habitat loss rather than over-hunting. Other studies that have assessed the effects of roads, habitat destruction, and hunting have shown similar results (Cullen, Bodmer & Valladares Padua, 2000, Kumara & Singh, 2004, Laurance *et al.*, 2006, Laurance *et al.*, 2009, Michalski & Peres, 2005, Naughton-Treves, Mena, Treves *et al.*, 2003, Parry, Barlow & Peres, 2009, Peres, 2001, Riley, 2002, Rovero, Mtui, Kitegile *et al.*, 2012).

In dramatic contrast with the Auca road, the area of influence of the Maxus road exhibits little signs of habitat loss and fragmentation, emphasizing the effectiveness of restricting access to oil extraction roads, in terms of avoiding human colonisation and its accompanying processes of habitat deterioration. In spite of this, wildlife communities in this area have been impacted as suggested by the absence or lower abundance and biomass of several species. The reasons for this decline are probably complex and we can only suggest potential explanations. However, it is interesting that most of the species that contribute to this decline are common target species of the Waorani hunters that live along the Maxus road and include White-lipped and collared peccaries, spider and capuchin monkeys, and Salvin´s curassow, Spix´s guan (*Penelope jacquacu*), and common piping guan (*Pipile pipile*). These species have been shown to contribute between 54 and 84% of the biomass consumed by Waorani families living along this

12

road (Franzen, 2006). In this context, our data suggest that the wildlife decline along the Maxus

road could be related to the intensification of hunting by the Waorani. This conclusion is further

supported by the importance of these species in the market of the Kichwa community of

Pompeya, which receives wild meat from communities along the Maxus road and the Napo

River. Between 2005 and 2007, for example, peccaries and spider monkeys accounted for 55%

of the total biomass and 48% of the animals that were sold in this market (Suárez *et al.*, 2009).

The depletion of wildlife along this controlled road has been already suggested on the basis of

hunting profiles, which showed that the populations of spider monkey (*Ateles belzebuth*) and

howler monkey (*Alouatta seniculus*) were experiencing severe depletion in areas influenced by

older Waorani communities along other segments of the Maxus road (Franzen, 2006).

Exceptions to this pattern were the woolly monkey and the howler monkey; despite being

important species in the Waorani diet, these species were as abundant or even more abundant on

the Maxus road site than in the Control site. We attribute this difference to the fact that two of

our transects along the Maxus road ran through a primate research plot in which monkey hunting

by the Waorani was restrticted through an economic subsidy provided to Waorani families by a

research project. Thus, regarding these species, our data on the impact of the Maxus road are

confounded by the effects of this conservation subsidy focused on these two species. For the

remaining large species, our data from the Maxus road resemble patterns found by previous

research comparing Amazonian sites exposed to contrasting levels of hunting, where a decrease

of wildlife biomass has been reported in heavily hunted areas (Bonaudo *et al.*, 2005b, Cullen *et

al.*, 2000, Endo, Peres, Salas *et al.*, 2010, Peres, 2000a, Peres & Dolman, 2000), similar to the

42% biomass decline that we estimated for the Maxus road site.

13

The depletion of wildlife populations in the relatively intact forests along the Maxus road, recalls the "empty forest" syndrome (Dirzo & Miranda, 1990, Redford, 1992, Wilkie, Bennett, Peres *et al.*, 2011). According to this pattern, dramatic ecological changes could be expected in this area as a result of the decline of several species that play key roles in the dynamics of the vegetation such us peccaries, monkeys, and several species of cracids. From this perspective, our results suggest two important conclusions regarding the management and control approaches used for roads in oil extraction areas. On one hand, the control of access to newly opened roads can be very effective in terms of avoiding colonization and the ensuing changes in land-use that result in forest loss and fragmentation, as can be seen while comparing remaining forest cover along the Auca and Maxus roads. Moreover, the lack of an impact on forest cover suggests that other groups of non-hunted wildlife (e.g. small birds, amphibians) could benefit from road access control. On the other hand, it is clear that access control is not enough to protect local populations of large- and medium-bodied vertebrates, especially when the presence and operation of the road, in combination with the practices of the oil companies, promote drastic changes in the living conditions and subsistence activities of local people. In the specific case of the Waorani who live along the Maxus road, it has been shown that the economic and transportation subsidies from oil companies increase their participation in the bushmeat trade and expand the area influenced by their hunting practices (Suárez *et al.*, 2009). Together with the adoption of more effective hunting technologies, this change is the most likely explanation for the severely depleted wildlife community that we found in this area.

14

The conclusions that we have outlined in this paper could be questioned in two important aspects: First, the probability that the differences in wildlife communities reported here could result not from the contrasting management approaches of the two roads, but from the very different age of the two roads. Second, the impossibility of finding true replicates to ensure that our results are not just a particularity of the system that we studied. Although the first possibility, cannot be discarded just based on our data, land-use analysis in this area (GeoPlaDes, 2010) suggest that this might not be the case: while the Auca road exhibits a forest loss rate of roughly 4%/yr since its construction, the Maxus road has experienced a rate of only 0.33%/yr. Moreover, the forest loss pattern at the Auca road exhibits the typical "fish-bone" configuration that has been reported in other Amazonian forests where non-indigenous colonists use new roads to establish farms in pristine areas (Locklin & Haack, 2003, Oliveira de Filho & Metzger, 2006, Sierra, 2000, Skole & Tucker, 1993). In contrasts, the limited forest loss reported along the Maxus road is restricted to the immediate surroundings of the road axis. While the two areas are occupied by Waorani communities, the Auca road also experienced rapid occupation by non-indigenous colonist from other parts of the country and an ample expansion of the road system, two differences that can only be explained by the control regime implemented by the oil companies in the Maxus road, and the absence of similar measures in the Auca road.

Regarding the second limitation of our study, the lack of true replicates and the validity of the resulting conclusions, this is a factor that has been previously discussed in the context of wildlife studies (Johnson, 2002). In this regard, we support the idea that a different paradigm is needed while judging the validity of wildlife and conservation studies. In very real terms, the particularities of the social and ecological contexts mean that it is virtually impossible to find

15

true replicates for this kind of research. In our case, for example, even if we could find an

additional pair of roads with the same management approaches that we analyzed in the YBR,

differences in the ethnic groups inhabiting those areas, the social or economic drivers that

promote colonization, and even the community-relationship frameworks used by different oil

companies would render any strict statistical comparison irrelevant. The uniqueness of these case

studies, however, does not mean that we cannot learn from them. In fact, we argue that, by

documenting these case studies, we provide perspectives and highlight the challenges that are

likely to arise as wildlife managers and decision-makers are confronted with their own "unique"

ecological and socio-economic settings. From this point of view, we believe that wildlife

management in these complex systems can be informed more efficiently by the publication and

analysis of several case studies (meta-replication; Johnson, 2002), that from the execution of

strictly replicated studies that will demand armies of researchers and very long research times

that we cannot afford.

In the context of increasing conflict that will emerge as ecologically sensitive areas are targeted

for access to economically valuable resources such as natural gas, oil, or minerals, we suggest

that the conservation of wildlife and its habitats will depend heavily on decisions concerning the

construction and management of roads. The control of public access to oil roads can reduce the

colonization of new areas and the ensuing deforestation. Moreover, we cannot discard the

possibility that this practice may even protect plant communities and non-game wildlife species.

However, our results suggests that, given the indirect effects of oil industry on the economy and

cultural practices of local people, these roads can have significant impacts on wildlife and on the

ecological processes of their ecosystems. In this context, we conclude that, if at all possible,

16

construction of new roads in "pristine" areas should be avoided, as the most effective way to

reduce the risk of colonization and the long-term costs that would be associated with the control

of newly opened roads in ecologically or culturally sensitive areas. If road construction is indeed

unavoidable, access control policies should be implemented, but could be insufficient in terms of

precluding severe impacts on wildlife, especially in areas where the operation of new roads and

the interactions between local people and oil companies affect the subsistence practices of local

communities and their relationships with local wildlife and ecosystems. From this point of view,

our study points out the urgent need to explore more responsible practices and regulations for the

interactions between local communities and industry, in which the indirect effects (*e.g.* access to

markets, improved transportation, cash economy) are taken into account and evaluated explicitly

regarding their impacts on wildlife.

Acknowledgements

Literature Cited

Ayres, M.*, et al.* (1991). On the track of the road: Changes in subsistence hunting in a brazilian amazonian village. In: *Neotropical wildlife use and conservation*: 53-81. Robinson, J. G. , Redford, K. H. (Eds.). Chicago: The University of Chicago Press.

17

Balslev, H. , Renner, S. S. (1989). Diversity of east ecuadorian lowland forests. In: *Tropical forests: Botanical dynamics, speciation, and diversity*: 287-295. Holm-Nielsen, L. B., Nielsen, L. C. , Balslev, H. (Eds.). London: Academic Press.

Bass, M*., et al.* (2010). Global conservation significance of ecuador's yasuní national park. *PLOS One,* **5:** e8767. doi:10.1371/journal.pone.0008767.

Benítez-López, A., Alkemade, R. , Verweij, P. A. (2010). The impacts of roads and other infrastructure on mammal and bird populations: A meta-analysis. *Biological Conservation,* **143:** 1307–1316.

Bonaudo, T*., et al.* (2005a). The effects of deforestation on wildlife along the transamazon highway. *European Journal of Wildlife Research,* **51:** 199-206.

Bonaudo, T*., et al.* (2005b). The effects of deforestation on wildlife along the transamazon highway. *European Journal of Wildlife Research,* **51:** 199-206.

Buckland, S. T*., et al.* (2001). *An introduction to distance sampling*. Oxford: Oxford University Press.

Campagna, C*., et al.* (2011). Gulf of mexico oil blowout increases risks to globally threatened species. *Bioscience,* **61:** 393-397.

Carrillo, E., Wong, G. , Cuarón, A. D. (2000). Monitoring mammal populations in costa rican protected areas under different hunting restrictions. *Conservation Biology,* **14:** 1580-1591.

Clevenger, A. P., Chruszcz, B. , Gunson, K. E. (2003). Spatial patterns and factors influencing small vertebrate fauna road-kill aggregations. *Biological Conservation,* **109:** 15-26.

Coelho, I. P., Kindel, A. , Coelho, A. V. P. (2008). Roadkills of vertebrate species on two highways through the atlantic forest biosphere reserve, southern brazil. *European Journal of Wildlife Research,* **54:** 689-699.

Cullen, L., Bodmer, E. R. , Valladares-Padua, C. (2001). Ecological consequences of hunting in atlantic forest patches, sao paulo, brazil. *Oryx,* **35:** 137-144.

Cullen, L., Jr., Bodmer, R. E. , Valladares Padua, C. (2000). Effects of hunting in habitat fragments of the atlantic forests, brazil. *Biological Conservation,* **95:** 49-56.

Delaune, R. D. , Wright, A. L. (2011). Projected impact of deepwater horizon oil spill on us gulf coast wetlands. *Soil Science Society of America Journal,* **75:** 1602-1612.

Dirzo, R. , Miranda, A. (1990). Contemporary neotropical defaunation and forest structure, function, and diversity - a sequel. *Conservation Biology,* **4:** 444-447.

Emmons, L. (1999). *Neotropical rainforest mammals: A field guide*. 2nd Ed. edn. Chicago: The University of Chigago Press.

Endo, W*., et al.* (2010). Game vertebrate densities in hunted and nonhunted forest sites in manu national park, peru. *Biotropica,* **42:** 251-261.

Finer, M*., et al.* (2009). Ecuador's yasuni biosphere reserve: A brief modern history and conservation challenges. *Environmental Research Letters,* **4**.

Forman, R. T. T. , Alexander, L. E. (1998). Roads and their major ecological effects. *Annual Review of Ecology and Systematics,* **29:** 207-+.

Franzen, M. , Eaves, J. (2007). Effect of market access on sharing practices within two huaorani communities. *Ecological Economics,* **63:** 776-798.

Franzen, M. A. (2006). Evaluating the sustainability of hunting: A comparison of harvest profiles across three huaorani communities. *Environmental Conservation,* **33:** 36-45.

18

Geoplades (2010). Estudio multitemporal de la cobertura vegetal y uso del suelo entre los años 1990, 2010 y proyección al 2030 a escala 1:50.000 para la amazonía ecuatoriana.). Quito: The Nature Conservancy and the Wildlife Conservation Society.

Godoy, R*., et al.* (2010). The effect of wealth and real income on wildlife consumption among native amazonians in bolivia: Estimates of annual trends with longitudinal household data (2002–2006). *Animal Conservation,* **13:** 265-274.

Goosem, M. (2002). Effects of tropical rainforest roads on small mammals: Fragmentation, edge effects and traffic disturbance. *Wildlife Research,* **29:** 277-289.

Greenberg, J. A*., et al.* (2005). Survival analysis of a neotropical rainforest using multitemporal satellite imagery. *Remote Sensing of Environment,* **96:** 202-211.

Hill, K*., et al.* (1997). Impact of hunting on large vertebrates in the mbaracayu reserve, paraguay. *Conservation Biology,* **11:** 1339-1353.

Johnson, D. H. (2002). The importance of replication in wildlife research. *The Journal of Wildlife Management,* **66:** 919-932.

Jones, M. E. (2000). Road upgrade, road mortality and remedial measures: Impacts on a population of eastern quolls and tasmanian devils. *Wildlife Research,* **27:** 289-296.

Kumara, H. N. , Singh, M. (2004). The influence of differing hunting practices on the relative abundance of mammals in two rainforest areas of the western ghats, india. *Oryx,* **38:** 321-327.

Laurance, W. F*., et al.* (2006). Impacts of roads and hunting on central african rainforest mammals. *Conservation Biology,* **20:** 1251-1261.

Laurance, W. F., Goosem, M. , Laurance, S. G. W. (2009). Impacts of roads and linear clearings on tropical forests. *Trends in Ecology & Evolution,* **24:** 659-669.

Locklin, C. C. , Haack, B. (2003). Roadside measurements of deforestation in the amazon area of bolivia. *Environmental Management,* **31:** 774-783.

Lopes, A. , Ferrari, S. F. (2000). Effects of human colonization on the abundance and diversity of mammals in eastern brazilian amazonia. *Conservation Biology,* **14:** 1658-1665.

Lu, F. E. (1999). *Changes in subsistence patterns and resource use of the waorani indians in the ecuadorian amazon.*, University of North Carolina.

Michalski, F. , Peres, C. A. (2005). Anthropogenic determinants of primate and carnivore local extinctions in a fragmented forest landscape of southern amazonia. *Biological Conservation,* **124:** 383-396.

Naughton-Treves, L*., et al.* (2003). Wildlife survival beyond park boundaries: The impact of slash-and-burn agriculture and hunting on mammals in tambopata, peru. *Conservation Biology,* **17:** 1106-1117.

Nepstad, D*., et al.* (2001). Road paving, fire regime feedbacks, and the future of amazon forests. *Forest Ecology and Management,* **154:** 395-407.

Ochoa, J. (2000). Effects of loggin on small-mammal diversity in the lowland forests of the venezuelan guyana region. *Biotropica,* **32:** 146-164.

Oliveira De Filho, F. J. B. , Metzger, J. P. (2006). Thresholds in landscape structure for three common deforestation patterns in the brazilian amazon. *Landsc. Ecol.,* **21:** 1061-1073.

Olsen, J. E. (2001). Environmental problems and ethical jurisdiction: The case concerning texaco in ecuador. *Bussiness Ethics,* **10:** 71-77.

Parry, L., Barlow, J. , Peres, C. A. (2009). Allocation of hunting effort by amazonian smallholders: Implications for conserving wildlife in mixed-use landscapes. *Biological Conservation,* **142:** 1777-1786.

19

Peres, C. (2001). Synergistic effects of subsistence hunting and habitat fragmentation on amazonian forest vertebrates. *Conservation Biology,* **15:** 1490-1505.

Peres, C. , Lake, I. R. (2003). Extent of nontimber resource extraction in tropical forests: Accesibility to game vertebrates by hunters in the amazon basin. *Conservation Biology,* **17:** 521-535.

Peres, C. A. (1999). Generalized guidelines for standardizing line-transect surveys of tropical forest primates. *Neotropical Primates,* **7:** 11-16.

Peres, C. A. (2000a). Effects of subsistence hunting on vertebrate community structure in amazonian forests. *Conservation Biology,* **14:** 240-253.

Peres, C. A. (2000b). Evaluating the impact and sustainability of subsistence hunting at multiple amazonian forest sites. In: *Hunting for sustainability in tropical forest*: 31-56. Robinson, J. G. , Bennett, E. L. (Eds.). New York: Columbia University Press.

Peres, C. A. , Dolman, P. M. (2000). Density compensation in neotropical primate communities: Evidence from 56 hunted and nonhunted amazonian forests of varying productivity. *Oecologia,* **122:** 175-189.

Redford, K. H. (1992). The empty forest. *Bioscience,* **42:** 412-422.

Richards, J*., et al.* (2011). Effects of the anthropogenic april 2010 bp deepwater horizon crude oil spill on seaweed diversity in the gulf of mexico. *Journal of Phycology,* **47:** S75-S75.

Riley, J. (2002). Mammals on the sangihe and talaud islands, indonesia, and the impact of hunting and habitat loss. *Oryx,* **36:** 288-296.

Rovero, F*., et al.* (2012). Hunting or habitat degradation? Decline of primate populations in udzungwa mountains, tanzania: An analysis of threats. *Biological Conservation,* **146:** 89-96.

Sierra, R. (2000). Dynamics and patterns of deforestation in the western amazon: The nape deforestation front, 1986-1996. *Applied Geography,* **20:** 1-16.

Skole, D. , Tucker, C. (1993). Tropical deforestation and habitat fragmentation in the amazon - satellite data from 1978 to 1988. *Science,* **260:** 1905-1910.

Southworth, J*., et al.* (2011). Roads as drivers of change: Trajectories across the tri-national frontier in map, the southwestern amazon. *Remote Sensing,* **3:** 1047-1066.

Spellerberg, I. F. (1998). Ecological effects of roads and traffic: A literature review. *Global Ecology and Biogeography,* **7:** 317-333.

Suárez, E*., et al.* (2009). Oil industry, wild meat trade, and roads: Indirect effects of oil extraction activities in a protected area in northeastern ecuador. *Animal Conservation,* **12:** 364-373.

Taylor, B. D. , Goldingay, R. L. (2010). Roads and wildlife: Impacts, mitigation and implications for wildlife management in australia. *Wildlife Research,* **37:** 320-331.

Thibault, M. , Blaney, S. (2003). The oil industry as an underlying factor in the bushmeat crisis in central africa. *Conservation Biology,* **17:** 1807-1813.

Thomas, L*., et al.* (2010). Distance software: Design and analysis of distance sampling surveys for estimating population size. *Journal of Applied Ecology,* **47:** 4-14.

Valdivia, G. (2007). The "amazonian trial of the century": Indigenous identities, transnational networks, and petroleum in ecuador. *Alternatives,* **32:** 41-72.

Vickers, W. T. (1988). Game depletion hypothesis of amazonian adaptation: Data from a native community. *Science,* **239:** 1521-1522.

Wilkie, D*., et al.* (2011). The empty forest revisited. *Annals of the New York Academy of Sciences,* **1223:** 120-128.

20

Wunder, S. (1997). From dutch disease to deforestation - a macroeconomic link? A case study from ecuador. *CDR Working Papers*.

Yoder, B. (2002). Indigenous people and oil production in ecuador's oriente. *Fourth World Journal,* **5:** 80-97.

Yost, J. A. , Kelley, P. M. (1983). Shotguns, blowguns, and spears: The analysis of technological efficiency. In: *Adaptive responses of native amazonians*: 189-224. Hames, R. B. , Vickers, W. T. (Eds.). London: Academic Press.

21

Table 1. Population density estimates for wildlife species recorded though direct observations along line transects established in the area of influence of two oil extraction roads (Auca and Maxus), and a Control site in Yasuní Biosphere Reserve. The two roads differ in their management approach from open-access and no control for the Auca road, to controlled access for the Maxus road. *D*: density of individuals/km^2; CI: 95% confidence interval.

	Control		Auca road		Maxus road	
	D	95% CI	D	95% CI	D	95% CI
Primates						
Alouatta seniculus	0	-	0	-	0.825	(0.161-4.220)
Ateles belzebuth	21.476	(8.549-53.953)	0	-	6.534	(1.805-23.649)
Callicebus moloch	7.46	(3.886-14.323)	0	-	3.095	(1.044-9.171)
Cebus albifrons	9.766	(4.189-22.768)	7.982	(2.652-24.028)	4.952	(1.368-17.923)
Lagothrix lagotricha	17.253	(9.545-31.187)	0	-	17.496	(8.664-35.331)
Pithecia monachus	1.809	(0.617-5.300)	3.942	(1.518-10.239)	1.834	(0.517-6.504)
Saguinus fuscicollis	0	-	0	-	0.825	(0.161-4.220)
Saguinus tripartitus	12.193	(5.652-26.306)	11.39	(4.345-29.858)	21.197	(10.221-43.957)
Saimiri sciureus	28.621	(13.767-59.498)	11.697	(3.276-41.767)	32.652	(14.383-74.122)
Artiodactyla						
Mazama americana	0.608	(0.156-2.374)	0	-	0.462	(0.090-2.364)
Pecari tajacu	2.448	(0.809-7.408)	0.8	(0.156-4.091)	0.745	(0.146-3.807)
Tayassu pecari	115.597	(41.984-318.275)	0	-	0	-
Rodentia						
Cuniculus paca	0.586	(0.115-2.998)	0	-	0	-
Dasyprocta fuliginosa	2.345	(0.908-6.059)	1.917	(0.542-6.776)	0	-

22

Microsciurus flaviventer	0.586	(0.115-2.998)	0	-	0.892	(0.174-4.560)
Myoprocta pratti	1.173	(0.332-4.145)	1.917	(0.542-6.776)	0.892	(0.174-4.560)
Sciurus spp.	11.214	(6.699-18.771)	8.147	(3.998-16.602)	5.686	(2.548-12.688)
Galliformes						
Mitu salvini	11.372	(5.669-22.812)	0	-	0	-
Nothocrax urumutum	0	-	1.377	(0.269-7.041)	0	
Ortalis guttata	0.421	(0.082-2.154)	0	-	0	-
Penelope jacquacu	10.108	(5.637-18.125)	2.361	(0.663-8.403)	3.295	(1.119-9.702)
Pipile pipile	6.706	(3.299-13.635)	3.654	(1.229-10.868)	1.133	(0.222-5.796)
Gruiformes						
Psophia crepitans	2.205	(0.603-8.061)	1.802	(0.352-9.215)	5.031	(1.650-15.343)
Piciformes						
Ramphastos spp.	1.029	(0.285-3.707)	0	-	3.13	(1.175-8.336)

23

Table 2. Average biomass estimates of wildlife recorded though direct observations along line transects established in the area of influence of two oil extraction roads (Auca and Maxus), and a Control site in Yasuní Biosphere Reserve. The two roads differ in their management approach from open-access and no control on the Auca road, to controlled access on the Maxus road.

Species	Biomass/individual (kg)	Total biomass/km^2		
		Control	Auca road	Maxus road
Tayassu pecari	33.50	3872.5	0.0	0.0
Ateles belzebuth	8.00	171.8	0.0	52.3
Lagothrix lagotricha	8.00	138.0	0.0	140.0
Pecari tajacu	20.00	49.0	16.0	15.0
Mitu salvini	3.10	35.3	0.0	0.0
Cebus albifrons	2.50	24.4	20.0	12.4
Saimiri sciureus	0.80	22.9	9.4	26.1
Mazama americana	22.10	13.4	0.0	10.2
Dasyprocta fuliginosa	3.60	8.4	6.9	0.0
Penelope jacquacu	0.75	7.6	1.8	2.5
Callicebus moloch	1.00	7.5	0.0	3.1
Sciurus spp.	0.57	6.4	4.6	3.2
Saguinus tripartitus	0.50	6.1	5.7	10.6
Cuniculus paca	7.80	4.6	0.0	0.0
Pithecia monachus	2.50	4.5	9.9	4.6

24

Psophia crepitans	1.20	2.6	2.2	6.0
Myoprocta pratti	0.71	0.8	1.4	0.6
Ramphastos spp.	0.75	0.8	0.0	2.3
Ortalis guttata	0.50	0.2	0.0	0.0
Microsciurus flaviventer	0.09	0.1	0.0	0.1
Alouatta seniculus	6.00	0.0	0.0	5.0
Saguinus fuscicollis	0.50	0.0	0.0	0.4
Nothocrax urumutum	2.50	0.0	3.4	0.0
Total		4381.94	83.88	295.25

25

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60

Figure Legends

Figure 1. Map of the study area, including all the localities included in the text. Only the northern

section of Yasuní National Park and the Waorani Ethnic Reserve are shown in the inset map.

Figure 2: The detection function superimposed on histograms showing the frequency of counts in

each distance interval with data pooled by order for the (a) Primates – uniform key function with

polynomial adjustment terms with right truncation at 25 meters, (b) Artiodactyla – half-normal

with no adjustment terms with right truncation at 35 meters and data grouped into four intervals

for analysis. (c) Galliformes – half-normal with no adjustment terms with right truncation at 20

meters (d) Galliformes + Gruiformes – uniform with cosine adjustment terms with right

truncation at 20 meters (e) Galliformes + Gruiformes – (f) Rodentia – half-normal with no

adjustment terms with right truncation at 15 meters.

26

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49

Figure 1

27

Figure 2.